

Remodel / Cabinets Already Installed Checklist**Before ordering:**

- Range/cooktop width measured
- Space between cabinets measured (wall-mount) or island width confirmed
- Ceiling height measured
- Desired hood height above cooktop determined
- Arched apron height consideration added (+3" if applicable)
- Apron molding width consideration added (up to +4" if applicable)
- Hood depth selected (21" or 24")
- Electrical outlet location verified
- Ductwork exit location confirmed
- Duct size confirmed (6", 7", 8", or 10")
- Hood projection checked against cabinet depth
- Backsplash pattern/layout considered (if applicable)

After ordering hood:

- Shop drawings reviewed and approved
- Final dimensions confirmed
- Based on hood design, verify electrical location with Marc
- Delivery timeline coordinated with installation schedule
- Installer lined up (if not DIY)

New Construction / Full Renovation Checklist**Before finalizing cabinet drawings:**

- Hood style selected (at least narrowed to 2-3 options)
- Hood width determined based on range size
- Mounting type confirmed (wall or island)
- Ceiling height measured
- Ductwork routing planned with HVAC contractor
- Electrical outlet location planned (behind hood, recommended positioning of the junction box is 8" up from the bottom of the hood and 12" to the right.
- Cabinet spacing coordinated with hood dimensions (including molding!)

Before ordering hood:

- Final style selected
- Measurements double-checked
- Based on hood design, verify electrical location with Marc
- Finish/texture chosen
- Ventilation specs confirmed (CFM, duct size, duct location)
- Lead time confirmed (currently 7-9 weeks)

Questions or Ready to Order?**Call Marc Today at 866-672-3401**